

Chapter 18

Transport and Traffic

18.0 Transport and Traffic

This chapter describes the potential impact of the Project on existing transport infrastructures including:

- road networks (State-controlled roads and local authority roads)
- · aerodromes and flight paths
- railways.

The overall methodology adopted for the impact assessment is listed below.

- Identification of the existing transport infrastructure in the vicinity of or traversed by the Draft Alignment.
- Assessment of the potential major transport route to the Project.
- Estimation of the project related construction and operational traffic volumes and anticipated vehicle movements.
- Identification of the potential impact and mitigation measures to be implemented during construction and operational phases.

18.1 Methodology

18.1.1 Key assumptions and development principles

During the construction and operational phases, it is understood that the Project will function as defined below.

- Construction work is expected to occur from July 2019 to December 2020 (18 construction months).
- Subject to availability, construction materials (i.e. gravel, concrete, sand etc.) and equipment/machinery will be preferentially sourced from local regional cities or townships such as Townsville and Charters Towers.
- Structure steel, conductors, and hardware will be imported internationally, via Brisbane or Townsville ports.
- All construction materials, equipment and machinery will be delivered to site via the road network.
- For construction of the transmission line, 2 to 3 temporary accommodation camps will be provided to accommodate approximately 300 construction personnel. The precise location of the camps is still to be determined but is generally planned to have one camp in the following areas –
 - Mt Fox Substation Site (40 person)
 - between Mt Fox and Greenvale (120 person)
 - between Greenvale and Kidston (120 person).
- The majority of construction personnel will be travelling from Townsville to the Project site or temporary accommodation camps via the road network.
- Construction personnel may be employed locally, i.e. from Greenvale, Ingham, Townsville and Charters Towers.
- Operational phase involves the following:
 - routine inspections and maintenance of the transmission line and substations
 - easement maintenance (i.e. vegetation clearing).

18.1.2 Limitations

This high-level impact assessment has been prepared based on the available information. The outcomes of this assessment should be read in conjunction with the following limitations and exclusions.

- This transport and traffic impact assessment is a desktop review exercise.
- This assessment does not include intersection assessment (i.e. sight distance checks, SIDRA modelling etc).
- This assessment excluded detailed design of road sections, intersection mitigation works or accesses.
- A site visit has not been undertaken to gauge the existing condition of the relevant transport infrastructures.

It must be noted that the purpose of this assessment, undertaken as part of the EAR, is not to define the exact quantity or nature of the traffic impact, for which further detailed traffic assessment is required. Rather, the purpose of this assessment is to highlight potential transport infrastructure impacts which may require further investigation and discussion with the relevant authorities.

18.2 Existing Environment

Figure 18-1 shows the existing transport infrastructure in the vicinity of or traversed by the Draft Alignment.

18.2.1 Road networks

The road network in the vicinity of the Draft Alignment includes both State-controlled roads and local authority roads. The State-controlled roads are under the management of the Department of Transport and Main Roads (DTMR) of three (3) different districts; North West District, Far North District and Northern District. The local authority roads are under the management of Etheridge Shire Council (ESC), Charters Towers Regional Council (CTRC) and Hinchinbrook Shire Council (HSC).

18.2.1.1 State-controlled road networks

The Draft Alignment for the transmission line intersects the following State-controlled roads as shown in Figure 18-1:

- 1. Kennedy Developmental Road
- 2. Gregory Developmental Road.

The section of Kennedy Developmental Road connects Hughenden to the south and Mount Garnet to the north. The section of Gregory Developmental Road connects Charters Towers to the south and Kennedy Developmental Road to the north.

18.2.1.2 Local authority road networks


The Draft Alignment traverses several locally administered major and minor roads as shown in Table 18-1 and Figure 18-1. These local roads are comprised mainly of unsealed roads and roads that have been gazetted, however unformed or undeveloped. A number of tracks used for property access or maintenance purposes are also traversed by the Draft Alignment. These tracks are typically soil aggregate construction.


Table 18-1 Local authority roads crossed by the Draft Alignment (from west to east)


Road Name	Road Characteristics			
Etheridge Shire Council				
Gilberton Road	Formed, unsealed			
Rycon Road	Formed, unsealed			
Proposed Road	Undeveloped road reserve			
Charters Towers Regional Council				
Unknown Road 1	Formed, unsealed			
Greenvale Valley Road	Formed, unsealed			
Unknown Road 2	Formed, unsealed			
Craiglee Road	Formed, unsealed			
Gadara Road	Formed, unsealed			
Proposed Road	Undeveloped road reserve			
Lava Plains Mount Fox Road	Formed, unsealed			
Lava Plains Mount Fox Road	Undeveloped road reserve			
Kangaroo Hills Road	Formed, unsealed			
Kallanda Road	Formed, unsealed			
Ewan Mount Fox Road	Undeveloped road reserve			
Hinchinbrook Shire Council				
Furber Road	Formed, unsealed			


18.2.2 Rail networks


No railway lines are traversed by the Draft Alignment. An abandoned railway line (known as The Greenvale Line) was identified in the proximity of the Draft Alignment near Greenvale township. The abandoned railway line runs southeast from the township of Greenvale to Townsville and connects an old mine to the Queensland Nickel Industries processing plant at Yabulu.


























18.2.3 Aerodromes and flight paths

A search for existing aerodromes and flight paths was conducted via the Queensland Spatial Catalogue (QSpatial) website and Queensland Globe – Transportation. No certified aerodromes were found in close proximity to the Draft Alignment (Figure 18-1). However, the following airstrips were identified via QSpatial website:

- Kidston airstrip –approximately 3 km north of the Draft Alignment
- Landing ground –approximately 3 km north of the Draft Alignment
- Greenvale airstrip –approximately 1.8 km south of the Draft Alignment
- Landing ground –approximately 7 km north of the Draft Alignment
- Landing ground –approximately 1.6 km south of the Draft Alignment
- Landing ground –approximately 1.9 km south of the Draft Alignment
- Landing ground –approximately 4 km north of the Draft Alignment
- Landing ground –approximately 1.2 km north of the Draft Alignment
- Landing ground –approximately 7 km south of the Draft Alignment
- Landing ground –approximately 7.6 km south of the Draft Alignment.

In accordance with Queensland Globe – Transportation, no regulated air service routes are in the vicinity of the Draft Alignment.

Activities such as aerial crop spraying, recreational flying, aerial mustering etc. may exists in close proximity to the Draft Alignment. This will be confirmed by Powerlink through consultation with the landholders or relevant authority.

18.2.4 Anticipated regional transport routes

It is anticipated that the majority of the traffic travelling to the Project site will originate from Brisbane and Townsville. The generated traffic includes the transportation of machinery, materials, equipment and personnel during both the construction and operation phases.


Through consultation with Powerlink Queensland, the major transport routes for access to the Draft Alignment for construction and operational activities are anticipated to be via the following two routes.

- Route 1 (Brisbane to Project Site) via Port of Brisbane Motorway, Cunningham Highway, Warrego Highway, Carnarvon Highway, Dawson Highway, Gregory Highway, Flinders Highway, Gregory Developmental Road, Greenvale Valley Road, Craiglee Road and newly constructed access tracks.
- Route 2 (Townsville to Project Site) via Hervey Range Road, Gregory Developmental Road, Greenvale Valley Road, Craiglee Road and newly constructed access tracks.
- Route 3 (Townsville to Project site) via Flinders Highway, Gregory Developmental Road, Greenvale Valley Road, Craiglee Road and newly constructed access tracks.

The anticipated major transport routes are illustrated in Figure 18-2 (State-controlled) and Figure 18-3 (local authority roads).

Access to the various work sites for construction materials, plant and personnel will use existing property access tracks where possible. Any new access tracks will be identified in consultation with landholders.





18.2.4.1 State-controlled roads

The latest traffic census data (2017) for the major state-controlled transport routes was sourced from DTMR, including the Annual Average Daily Traffic (AADT) and percentage of heavy vehicles (HV%). This traffic data is summarised in Table 18-2.

Table 18-2 Major transport routes (State-controlled road) traffic data and road characteristics

Road Name	Section	Traffic count Site	2017 AADT	Percentage of HV
			veh/day	%
Port of Brisbane Motorway		136238	10,860	42.20%
Cunningham	Ipswich Motorway	140035	108,841	4.00%
Highway		140027	114,272	Not available
		136081	101,306	Not available
Warrego	Ipswich - Toowoomba	135546	57,860	14.17%
Highway		135715	44,933	15.31%
		135964	32,906	14.70%
		10021	30,136	19.43%
		30066	22,707	19.07%
		30041	15,731	20.11%
		30070	20,059	17.62%
		32636	24,605	17.94%
		37610	16,813	23.36%
		32686	17,638	20.24%
Warrego	Toowoomba - Dalby	30071	21,905	13.22%
Highway		37608	14,468	18.52%
		30074	10,806	7.81%
		30075	20,175	7.92%
		32645	14,697	11.72%
		30025	12,602	17.42%
		32641	9,988	18.18%
		32559	5,125	22.62%
		30004	5,520	26.08%
		30012	7,492	23.20%
		32693	11,609	16.40%
Warrego	Dalby - Miles	32633	8,628	21.08%
Highway		32647	4,141	28.81%
		30040	2,988	29.23%
		30076	2,963	30.02%
		32047	2,854	27.97%
		32654	3,134	27.10%
		32648	6,034	22.97%
		32048	4,866	24.43%
		30020	3,106	30.87%

Road Name	Section	Traffic count Site	2017 AADT	Percentage of HV
		40047	2,704	29.59%
Warrego Highway	Miles - Roma	40250 40405 40320 40542 40155 40631 40502	3,689 1,966 1,606 1,550 1,980 3,064 4,248	29.08% 28.85% 33.02% 39.24% 30.54% 26.51% 25.63%
Carnarvon Highway	Roma - Injune	40513 40514 40171	2,481 1,273 822	20.97% 32.69% 38.10%
Carnarvon Highway	Injune - Rolleston	40334 150017 159561	568 577 569	41.83% 26.64% 29.98%
Dawson Highway	Rolleston - Springsure	159672 150021 159663 159665	556 656 1,330 1,452	19.92% 30.17% 18.06% 11.57%
Gregory Highway	Springsure - Emerald	159668 159667 150022 159639 159609	1,451 1,224 1,555 2,785 5,785	10.20% 21.92% 22.59% 10.57% 11.12%
Gregory Highway	Emerald - Clermont	159706 159699 159675 150025 159598 159653 159652 159651 150015	8,201 9,859 4,485 2,715 1,849 2,336 1,620 1,323 1,154	10.62% 9.98% 18.70% 23.13% 20.04% 15.61% 21.24% 25.29% 28.22%
Gregory Highway	Clermont - Belyando Crossing	159536 159640	1,715 1,525	22.70% 14.62%
Gregory Developmental Road	Clermont - Belyando Crossing	159538 150016	641 425	28.41% 33.79%
Gregory Developmental Road	Belyando Crossing - Charters Towers	90020 91701	323 674	39.69% 10.75%

Road Name	Section	Traffic count Site	2017 AADT	Percentage of HV
Flinders Highway	Townsville to Charters	92192	1,923	38.63%
	Towers	90060	6,622	30.10%
		91389	2,367	21.97%
		91328	1,683	27.84%
		91329	2,648	20.67%
Gregory	Charters Towers to	91298	1,462	11.81%
Developmental	Project site	91327	2,882	7.31%
Road		90087	668	16.88%
		90002	235	42.68%
		91702	203	33.55%
Hervey Range	Townsville to Gregory	91554	15,963	2.01%
Road	Developmental Road	90013	13,686	4.94%
		92238	11,516	7.49%
		92223	12,032	5.26%
		91459	7,311	5.37%
		91461	4,921	9.85%
		90065	1,413	17.95%
		90066	1,101	13.77%
		91464	222	28.33%
		91424	156	31.23%

In accordance with DTMR's Multi-Combination Routes Maps (Figure 18-4 to Figure 18-9):

- Port of Brisbane Motorway designated B-doubles route
- Cunningham Highway designated B-doubles
- Warrego Highway designated B-doubles/Type 1 Road Train route
- Carnarvon Highway designated B-doubles/Type 1 Road Train route
- Dawson Highway designated B-doubles/Type 1 Road Train route
- Gregory Highway designated B-doubles/Type 1 Road Train route
- Gregory Developmental Road designated B-doubles/Type 1 & 2 Road Train route
- Hervey Range Road designated B-doubles/Type 1 Road Train route
- Flinders Highway designated B-doubles/Type 1 & 2 Road Train route.




Figure 18-4 DTMR Multi-Combination Route Map (View 1)




Figure 18-5 DTMR Multi-Combination Route Map (View 2)




Figure 18-6 DTMR Multi-Combination Route Map (View 3)




Figure 18-7 DTMR Multi-combination Route Map (View 4)




Figure 18-8 DTMR Multi-combination Route Map (View 5)




Figure 18-9 DTMR Multi-combination Route Map (View 6)




Figure 18-10 DTMR Multi-Combination Route Map (View 7)

It is noted that the following projects are currently underway on the anticipated major State-controlled transport routes.

Warrego Highway Upgrade Program: Chinchilla Open Level Crossing upgrade

The open level crossing project covers the section of road where the western Queensland rail line intersects with the Warrego Highway and Wambo Street. Construction of this project is expected to begin in late 2018.

Warrego Highway Upgrade Program: Dalby-Miles overtaking lanes

The project provides additional overtaking lanes at regular intervals, in both directions, between Dalby and Miles. The project aims to improve road safety and freight efficiency and support the ongoing development of the Surat Basin by constructing 7 overtaking lanes (4 westbound and 3 eastbound), at 4 locations between Dalby and Miles. The new lanes will provide additional opportunities for safe overtaking and reduce road congestion for road users. Construction commenced in January 2018 and is expected to take about 12 months to complete.

Warrego Highway Upgrade Program: Oakey to Miles safety upgrade

The project aims to improve the safety of all road users by reducing the incidence of fatal or serious injury crashes on the Warrego Highway. The project consists of wide centreline treatment, pavement repairs, road formation widening, intersections upgrade etc. The project commenced in February 2017 and expected to be completed in mid-2019.

<u>Flinders Highway Widening (Townsville – Torrens Creek)</u>

Pavement widening and strengthening on the Flinders Highway between Townsville and Torrens Creek, at Mingela and Sellheim. The construction commenced in June 2018 and is due to be completed in mid-2019.

Gregory Developmental Road pavement widening—Belyando Crossing to Charters Towers

Widening narrow sections on the Gregory Developmental Road, between Belyando Crossing and Charters Towers (from Sardine Creek to Boomerang Creek). The project will deliver significant improvements for motorists, by strengthening and widening the existing pavement and bitumen seal, between Charters Towers and Belyando Crossing. Construction is expected to start in early 2019 and be completed by mid-2019.

Gregory Developmental Road (Charters Towers to The Lynd)

Pavement widening and strengthening across 8 work sites on the Gregory Developmental Road, between Charters Towers and The Lynd. The construction commenced in June 2017 and is expected to be completed in late 2019.

18.2.4.2 Local authority roads

Craiglee Road and Greenvale Road are within the proposed main transport routes under CTRC jurisdiction. The average road width of these roads is between 4m to 7m wide (measured off Google Earth). The traffic count data was not available during this assessment. Given that these local roads mainly provide access to local properties, it is anticipated that the traffic volume is relatively low. The daily traffic volume for these roads has been conservatively estimated to be 10 vehicles per day.

18.3 Potential Impacts

18.3.1 Project-related traffic (construction and operational)

18.3.1.1 Construction phase

The construction phase of the Project is currently anticipated to be undertaken over an 18 month period, proposed to commence in July 2019 and be completed in December 2020. It is noted that the dates and timeframes adopted for this assessment are indicative only and subject to change.

The anticipated Project construction traffic volumes will largely depend on the selected construction contractor and Project scheduling. Project-related traffic during construction will mainly comprise of:

- regional movement of materials and equipment that cannot be sourced locally and most likely brought from Brisbane, i.e. insulators, structure steel, conductors, over-dimensioned materials.
- local movement of construction personnel between Townsville and temporary accommodation camps.
- local movement of construction material and equipment (i.e. concrete batching plant, construction and earthworks machinery), the majority of which is expected to be sourced from Townsville.

A combination of State-controlled and local authority road networks will be used to access construction sites. Section 18.2.3 indicates the key roads which are anticipated to be subject to the Project construction traffic.

1) Regional movement of materials and equipment

Materials and equipment will predominantly be delivered to site from Brisbane, via the western route (Cunningham Highway, Warrego Highway, Carnarvon Highway, Dawson Highway, Gregory Highway, Flinders Highway, Gregory Developmental Road). Based on previous experience on similar transmission line projects Powerlink estimated heavy vehicle traffic may reach up to 16 heavy vehicle and 10 light vehicle movements monthly (two-way trips).

2) <u>Local movement of construction personnel between Townsville and temporary accommodation</u> camps

Based on the information provided by Powerlink, the anticipated number of construction workers on site will be in the order of 300 staff on a 2/1 roster, hence approximately 200 staff on site at any given time. It is understood that all construction staff movements will be made to/from Townsville and the temporary accommodation camps using 50 seat passenger buses. During roster changes staff will be transported via Hervey Range Road and Gregory Developmental Road due to short travel distance. The daily traffic during roster change was estimated to be approximately 8 heavy vehicle (bus) round trip per day.

3) Local movement of construction material and equipment

Heavy vehicles delivering construction materials and equipment to site (i.e. concrete batching plant, construction and earthworks machinery), will be sourced from Townsville, via the Flinders Highway and Gregory Developmental Road. Please note that this traffic will predominantly occur during the mobilisation and demobilisation phases of the construction phase. Hence, the majority of heavy vehicles will reside on site throughout the construction period and operate along the proposed works corridor. Based on our previous experience with similar transmission line projects and through discussion with Powerlink, the estimated heavy vehicle traffic may reach up to 12 heavy vehicle movements daily (two-way trips).

Local authority roads including Craiglee Road and Greenvale Valley Road at Greenvale township, will serve to connect Gregory Development Road to the transmission line alignment.

As mentioned earlier, majority of the anticipated construction traffic movements only occur on an occasional basis and not on a daily basis. Hence, the following daily traffic volumes were conservatively adopted for the impact assessment purposes.

- Regional movement of materials and equipment 6 heavy vehicle and 6 light vehicle round trip per day.
- Local movement of construction personnel 8 heavy vehicle round trip per day.
- Local movement of construction material and equipment 12 heavy vehicle round trip per day.

Please note that a Principal Contractor has not been appointed for this project, at the time of writing this report and once a contractor is in place, the assumptions contained within this document can be tested and the proposed traffic volumes can be confirmed.

18.3.1.2 Operation and maintenance phase

Vehicle movements during the operational and maintenance phase will generally consist of routine inspections and maintenance of the transmission lines and substation. The local authority road network will be used via the previously identified major transport routes. These traffic volumes will be considerably lower than those associated with the construction phase, and principally be limited to specific access tracks built for maintaining the transmission lines and substations. Easement access arrangements will be established with landholders, as required.

An indication of the anticipated operational traffic volumes for the Project is provided in Table 18-3. These figures are based on similar transmission line projects proportionate in scale with that of the Project.

Table 18-3 Indicative vehicle movements generated during operation and maintenance phase

Maintenance Activity	Frequency	Vehicles Required						
Transmission Line Maintenance								
Ground patrol	Once every three years	3 x four-wheel drives						
Aerial patrol	Once per year	2 x helicopters 2 x fuel trucks						
Footing resistance testing	Once every five years	6 x four-wheel drives						
Inspection of landing spans	Once every five years	6 x four-wheel drives 3 x elevated work platforms (i.e. cherry-picker)						
Insulator testing	Once every five years	6 x four-wheel drives 3 x elevated work platforms (i.e. cherry-picker)						
Corrective emergency patrols	(allow) three per year	2 x helicopters 2 x fuel trucks						

Maintenance Activity	Frequency	Vehicles Required
Corrective maintenance (fault investigation)	(allow) two per year	3 x four-wheel drives
Corrective maintenance (upgrade earthing)	(allow) 10 transmission line structures per year	3 x trench/backhoe 3 x four-wheel drive trucks 3 x four-wheel drives
Corrective maintenance (removal of bird nests)	(allow) 10 transmission line structures per year	6 x four-wheel drives 3 x elevated work platforms (i.e. cherry-picker)
Corrective maintenance (replacement of flashed insulators)	(allow) one string every five years	6 x four-wheel drives 3 x elevated work platforms (i.e. cherry-picker)
Easement Maintenance		
Rural vegetation management (targeted)	Once every six years	3 x four-wheel drive trucks 3 x four-wheel drives
Rural vegetation management (midterm treatment)	Once every six years	3 x four-wheel drive trucks 3 x four-wheel drives
Rural residential/urban vegetation management	Once per year	3 x four-wheel drive trucks 3 x four-wheel drives
Mechanical vegetation management	As required	3 x tractor/slasher 3 x four-wheel drive
Access track maintenance	As required	3 x graders 3 x four-wheel drives
General maintenance (e.g. weed control, rehabilitation works etc)	As required	3 x four-wheel drives
Land management inspections	Once every six months	3 x four-wheel drives
Substations Maintenance		
General maintenance (e.g. weed control)	As required	1 x four-wheel drive
Routine Maintenance	Twice per year	3 x four-wheel drives 1 x elevated work platforms

18.3.2 Road networks

18.3.2.1 Construction phase

State-controlled roads

In accordance with DTMR's Guide to Traffic Impact Assessment, Section 6.4, all road links where development traffic exceeds 5% of the base traffic (background traffic) is deemed to have an impact on the road network. A growth rate of 1% growth per annum has been adopted with a linear growth pattern to project the 2017 AADT to construction commencement year 2019.

The 5% trigger assessment of the Project traffic has been conducted and summarised in Table 18-5.

Table 18-4 Indicative vehicle movements generated during construction phase

		Backgrour	nd Traffic	Project Traffic			0/ of Duoings
Road Name	Section	Traffic count	2019 AADT	Light Vehicle	Heavy Vehicle	Total	% of Project Traffic to Background
		Site	veh/day	veh/day	veh/day	veh/day	Traffic
Port of Brisbane Motorway		136238	11,078	6	6	12	0.1%
Cunningham Highway	Ipswich Motorway	140035 140027 136081	111,029 116,569 103,342	6 6 6	6 6 6	12 12 12	0.01% 0.01% 0.01%
Warrego Highway	lpswich - Toowoomba	135546 135715 135964 10021 30066 30041 30070 32636 37610 32686	59,023 45,836 33,567 30,742 23,163 16,047 20,462 25,100 17,151 17,993	6 6 6 6 6 6 6 6	6 6 6 6 6 6 6 6 6	12 12 12 12 12 12 12 12 12 12	0.02% 0.03% 0.04% 0.14% 0.15 0.16 0.176 0.076 0.176 0.176
Warrego Highway	Toowoomba - Dalby	30071 37608 30074 30075 32645 30025 32641 32559 30004 30012 32693	22,345 14,759 11,023 20,581 14,992 12,855 10,189 5,228 5,631 7,643 11,842	6 6 6 6 6 6 6 6 6	6 6 6 6 6 6 6 6 6	12 12 12 12 12 12 12 12 12 12 12	0.1% 0.1% 0.1% 0.1% 0.1% 0.1% 0.2% 0.2% 0.2% 0.2%
Warrego Highway	Dalby - Miles	32633 32647 30040 30076 32047 32654 32648 32048 30020 40047	8,801 4,224 3,048 3,023 2,911 3,197 6,155 4,964 3,168 2,758	6 6 6 6 6 6 6 6	6 6 6 6 6 6 6 6 6	12 12 12 12 12 12 12 12 12 12	0.1% 0.3% 0.4% 0.4% 0.4% 0.2% 0.2% 0.4% 0.4%
Warrego	Miles - Roma	40250	3,763	6	6	12	0.3%

		Backgrour	nd Traffic	Project Traffic			
Road Name	Section	Traffic count	2019 AADT	Light Vehicle	Heavy Vehicle	Total	% of Project Traffic to Background
		Site	veh/day	veh/day	veh/day	veh/day	Traffic
Highway		40405	2,006	6	6	12	0.6%
		40320	1,638	6	6	12	0.7%
		40542	1,581	6	6	12	0.8%
		40155	2,020	6	6	12	0.6%
		40631	3,126	6	6	12	0.4%
		40502	4,333	6	6	12	0.3%
		40513	2,531	6	6	12	0.5%
Carnarvon	Roma -	40513	1,299	6	6	12	0.5%
Highway	Injune	40171	839	6	6	12	1.4%
		40171		0	O	12	1.4 /0
		40334	579	6	6	12	2.1%
Carnarvon Highway	Injune - Rolleston	150017	589	6	6	12	2.0%
riigiiway	Kollestori	159561	580	6	6	12	2.1%
		159672	567	6	6	12	2.1%
Dawson	Rolleston -	150021	669	6	6	12	1.8%
Highway	Springsure	159663	1,357	6	6	12	0.9%
		159665	1,481	6	6	12	0.8%
		159668	1,480	6	6	12	0.8%
		159667	1,249	6	6	12	1.0%
Gregory Highway	Springsure - Emerald	150022	1,586	6	6	12	0.8%
ligilway	Linerald	159639	2,841	6	6	12	0.4%
		159609	5,901	6	6	12	0.2%
		159706	8,366	6	6	12	0.1%
		159699	10,057	6	6	12	0.1%
		159675	4,575	6	6	12	0.3%
Crogory	Emerald -	150025	2,770	6	6	12	0.4%
Gregory Highway	Clermont	159598	1,886	6	6	12	0.6%
g	0.0	159653	2,383	6	6	12	0.5%
		159652	1,653	6	6	12	0.7%
		159651	1,350	6	6	12	0.9%
		150015	1,177	6	6	12	1.0%
Gregory	Clermont -	159536	1,749	6	6	12	0.7%
Highway	Belyando Crossing	159640	1,556	6	6	12	0.8%
Gregory Developmen	Clermont - Belyando	159538	654	6	6	12	1.8%
tal Road	Crossing	150016	434	6	6	12	2.8%
Gregory Developmen	Belyando Crossing -	90020	329	6	6	12	3.6%

	Section	Background Traffic		Project Traffic			% of Project
Road Name		Traffic count	2019 AADT	Light Vehicle	Heavy Vehicle	Total	Traffic to Background
		Site	veh/day	veh/day	veh/day	veh/day	Traffic
tal Road	Charters Towers	91701	688	6	6	12	1.7%
		92192	1,962	0	12	12	0.6%
	Townsville to	90060	6,755	0	12	12	0.2%
Flinders Highway	Charters	91389	2,415	0	12	12	0.5%
ligitway	Towers	91328	1,717	6	18	24	1.4%
		91329	2,701	6	18	24	0.9%
		91298	1,491	6	18	24	1.6%
Gregory	Charters	91327	2,940	6	18	24	0.8%
Developmen	Towers to	90087	681	6	18	24	3.5%
tal Road	Project site	90002	240	6	18	24	10.0%
		91702	207	6	26	32	15.5%
		91554	16,284	0	8	8	0.05%
		90013	13,961	0	8	8	0.1%
		92238	11,747	0	8	8	0.1%
	Townsville to	92223	12,274	0	8	8	0.1%
Hervey	Gregory	91459	7,458	0	8	8	0.1%
Range Road	Development	91461	5,020	0	8	8	0.2%
	al Road	90065	1,441	0	8	8	0.6%
		90066	1,123	0	8	8	0.7%
		91464	226	0	8	8	3.5%
		91424	159	0	8	8	5.0%

Based on the assessment, the estimated construction traffic volumes will have minimal impact on the proposed route during construction period except Gregory Developmental Road (Charters Towers to Project site). The estimated construction traffic exceeds 5% of the background traffic on Gregory Developmental Road (Charters Towers to Project site). Detailed traffic/pavement impact assessment will be necessary to assess the level of impact on these section roads, in terms of safety, access, intersection delay, road link capacity, pavement, bridges and culverts. Subject to the traffic/pavement impact assessment outcomes, further discussion with DTMR may be required to identify how to best mitigate the impact.

The transport of over dimensioned equipment/material (i.e. transformers) or hazardous/dangerous goods may be required on State-controlled roads. The relevant approvals and permits will be sought from DTMR.

Local Authority Roads

Based on the assessment, the estimated construction traffic volumes exceed 5% of the background traffic on Craiglee Road and Greenvale Road during construction. However, the traffic operation of these roads is unlikely to be impacted by the Project, given the low background traffic volumes and the temporary duration of the construction works.

Powerlink will work with each Council to agree on road use protocols including maintenance and remediation works if damage is caused by project traffic.

Temporary Road Closures

Temporary road closures may be required for safety during certain construction activities, such as conductor stringing. These will generally be for a short duration (i.e. during aerial stringing) and with appropriate traffic management plans and procedures in place, the traffic flow impacts on State-controlled roads and local authority roads will be minimal. Temporary road closures will not restrict emergency service vehicle movement.

Maintenance activities for the proposed transmission line and substations are not anticipated to significantly affect the road networks, property accesses or community amenities. Planned maintenance activities involving vegetation (regrowth) clearing to maintain safe electrical clearances and structure inspection will require vehicular access to and along the transmission line easement. The impacts of these maintenance activities will be minimal as they are infrequent, localised and of short duration (refer to frequency information provided in Table 18-3).

18.3.3 Rail networks

No railway lines are traversed by the Draft Alignment.

18.3.4 Aerodromes and flight paths

As indicated in Section 18.2.2, no certified aerodromes or regulated air service routes (of regional or State significance) are in close proximity to the Draft Alignment. Ten (10) airstrips were identified within 8 km of the Draft Alignment.

Consultation with the relevant authority or landholder of these airstrips would be deemed necessary to ensure no hazard or restriction is created by the Draft Alignment for landing, aerial spraying or mustering activities etc.

18.4 Mitigation and Management Measures

The following measures have been proposed to minimise the potential impacts from Project construction identified in Section 18.3.

- A detailed Traffic Management Plan for the Project to be developed and implemented prior to construction works commencing.
- Ensure that the movement of major vehicles carrying oversized components (such as transmission structure components) will be outside the times that school bus movements will occur and all key stakeholders are included in the communications regarding changed or impacted bus routes, including school bus operators, school bus committees, schools/parents and local authorities.
- Obtain local authority (i.e. local Council) approval for potential road closures or traffic delays to emergency services and the local community. Any temporary road closures will involve on site traffic management, so that in the event of emergency service vehicles needing to pass through the areas where stringing is occurring, passage will be provided.
- Apply for appropriate approvals and permits under the *Transport Infrastructure Act 1994* from DTMR for any permanent or temporary access to state control roads, including associated roadworks for access, the transport of over dimensioned equipment and materials on state control roads and for ancillary works and encroachments.
- Detailed planning to be undertaken for conductor stringing across State controlled and other
 regional roads in consultation with DTMR and relevant local authorities. All necessary approvals
 required from DTMR and local authorities for undertaking these works will be applied for and
 received prior to works commencing.
- Consideration where possible during Project planning, to undertake selected construction works likely to cause significant traffic disruption and delay at times of low traffic volumes or at night to minimise localised congestion and potential safety implications.
- Dedicate traffic management personnel for traffic management and safety purposes, particularly
 when construction works are being conducted close to roads or where lane closures are required.

- Road upgrade or rectification will be undertaken (as agreed between the relevant local authorities and Powerlink) where mitigation measures are required to address issues associated with the haulage of construction materials such as pavement degradation and insufficient road geometry.
- Consultation with the relevant authority or landholder of local airstrips may be necessary to implement controls to minimise hazards or restrictions created by the Draft Alignment for landing, aerial spraying or aerial mustering activities etc.

No specific mitigation measures are anticipated to be required for the operation and maintenance phase of the Project.